9 A2.40 New floor plan

Scale 1/8"=1'-0"

REVISED
8:45 am, Jan 22, 2024

KEY NOTES

1. Owner furnished carts
2. For additional door information, refer to drawing A9.01 for schedule
3. For additional room finish information, refer to drawing A9.01 for finish scheudle
4. Existing Electrical equipment
5. 42" by 20" Bench
6. Remove existing sheetrock at demising wall from floor to bottom of interstitial utility space, floor framing above. Infill with rock-wool sound attenuation. Recover exposed stud wall with two layers of 5/8" GBX.
7. Ladder Safety Post (Bilco LU-1 Ladder Safety Post, or approved equal)
8. Fixed Steel ladder (Cotterman Fixed Ladder, item 4EU33, Mfr. Model F15S C1, or approved equal)
9. 3X3 Roof hatch (Activar Model RHDG-4WT, or approved equal)- to attic space.

COPYRIGHT – LEEKA, INC. – ALL RIGHTS RESERVED

#5024 REGISTERED ARCHITECT Lee STATE OF WASHINGTON

LEEKA Architecture and Planning
Creating Positive Impressions in the Built Environment
503.644.4222 tel
success@leekainc.com e-mail
www.leekainc.com web
1001 SE Water Avenue Suite 175
Portland, Oregon 97214

Tenant Improvement
Educational Service District 112
Mental Health Facility Phase II
2400 NE 65th Ave. Vancouver WA.

Revised:	
PCR 01	DATE: Aug. 10, 2023
APPLICANT EDITS	DATE: Aug. 17, 2023
APPLICANT EDITS	DATE: Sept. 22, 2023
APPLICANT EDITS	DATE: Oct. 03, 2023
APPLICANT EDITS	

Job No: 2246
Date: 2-Jan-24
File Size: 24x36
Permit Application
DRAWN: NYL
CHECKED: NYL
Sheet Title
Floor Plan
Sheet Number
A2.40