

ADDENDUM ..... No. 01

SUBJECT ..... Additional Scope

DATE ISSUED..... February 8, 2024

- Include additional work in scope to complete new curbs for North window wall/store front infills to seat on.
- Include South window walls/store front infill sills flushing out with concrete fixall/ tapering grout in prep for new window walls and store fronts. No curbs at the south side infill openings. New window wall/store front infills to bear down directly on top of slab after flush troweling.
- Include saw cutting out bad sections that contain asphalt, removal, adding epoxy rebaring, and repouring of new curbs as shown on drawings.
- Door cutouts to be flush with existing interior floor, and flush sloped for new exterior sidewalk approaches.
- Drawings A6.01; A6.02; S3.01 (see detail #15/S3.01) available at <https://www.esd112.org/news/faq-items/civil-concrete-sidewalks-stair-landings-2400-phase-ii/>

**Important Note to Bidders:**

Only the items referenced in this addendum shall be revised. All other provisions, requirements, and terms and conditions of ITB ESD 112-31-23 shall remain the same.

**Instructions to Bidders:**

Bidders shall sign, date and submit the form on this page with the rest of your company's bid materials.

Name of Company \_\_\_\_\_

Name of Authorized Representative (Please print) \_\_\_\_\_

Signature of Authorized Representative \_\_\_\_\_

Date Signed \_\_\_\_\_

Thank you.



Jeff Strunk, Director of Purchasing & Facilities  
E-Mail: Jeff.Strunk@esd112.org